

Reinforced Concrete Maintenance Holes

SIZE (mm)	DESCRIPTION	HEIGHT (m)	APPROX. MASS	PRICE \$
1200	taper top c/w steps	1.320	1905 kg/pc	1,004.60 ea.
1200	flat cap	0.305	715 kg/pc	572.40 ea.
1200	riser c/w steps	0.305 to 1.829	1324 kg/m	732.00 /m
1200	monolithic base c/w steps	0.762	1760 kg/pc	1,209.50 ea.
1200	monolithic base c/w steps	0.914	1960 kg/pc	1,320.90 ea.
1200	monolithic base c/w steps	1.067	2160 kg/pc	1,432.80 ea.
1200	monolithic base c/w steps	1.372	2550 kg/pc	1,654.60 ea.
1200	monolithic base c/w steps	1.524	2750 kg/pc	1,766.00 ea.
1200	base slab	0.203	780 kg/pc	572.40 ea.
1200	safety grate supplied & installed			1,371.70 ea.
1200	prebenching			659.90 ea.
1500	flat cap	0.430	1810 kg/pc	1,140.50 ea.
1500 to 1200	transition c/w steps	0.610	1678 kg/pc	1,140.50 ea.
1500	riser c/w steps	3.05 to 2.438	1927 kg/m	1,109.50 /m
1500	monolithic base c/w steps	1.067	3430 kg/pc	2,660.60 ea.
1500	monolithic base c/w steps	1.372	4040 kg/pc	2,998.90 ea.
1500	monolithic base c/w steps	1.676	4645 kg/pc	3,336.20 ea.
1500	monolithic base c/w steps	1.829	5050 kg/pc	3,506.00 ea.
1500	monolithic base c/w steps	1.981	5350 kg/pc	3,674.70 ea.
1500	base slab	0.305	1770 kg/pc	1,140.50 ea.
1500	safety grate supplied & installed			1,931.40 ea.
1500	prebenching			888.00 ea.
1800	flat cap	0.430	2720 kg/pc	1,538.00 ea.
1800 to 1200	transition c/w steps	0.610	2400 kg/pc	1,538.00 ea.
1800	riser c/w steps	0.610 to 2.438	2756 kg/m	1,577.70 /m
1800	base slab	0.305	2630 kg/pc	1,538.00 ea.
1800	safety grate supplied & installed			2,506.20 ea.
2400	flat cap	0.430	4980 kg/pc	3,047.60 ea.
2400 to 1200	transition slab c/w steps	0.430	4210 kg/pc	3,047.60 ea.
2400	riser c/w steps	0.610 to 2.438	4598 kg/m	2,812.80 /m
2400	base slab	0.305	4620 kg/pc	3,047.60 ea.
2400	safety grate supplied & installed			3,919.00 ea.
3000	flat cap	0.450	7847 kg/pc	5,132.40 ea.
3000 to 1200	transition slab c/w steps	0.450	7258 kg/pc	5,132.40 ea.
3000	riser c/w steps	0.610 to 2.438	7043 kg/m	4,400.30 /m
3000	base slab	0.305	8225 kg/pc	5,132.40 ea.
3000	safety grate supplied & installed			on request
3600	flat cap	0.450	10500 kg/pc	9,063.00 ea.
3600 to 1200	transition slab c/w steps	0.450	10500 kg/pc	9,063.00 ea.
3600	riser c/w steps	0.610 to 1.829	11042 kg/m	9,589.70 /m
3600	base slab	0.305	10500 kg/pc	9,063.00 ea.
3600	safety grate supplied & installed			on request

IMPORTANT: 2400mm, 3000mm, and 3600mm MAINTENANCE HOLES TO BE OFF-LOADED BY CONTRACTOR.

NOTES:

- 1) Gaskets included in price.
- 2) Prices on product manufactured to OPSD 700 series and OPSD 1000 series.
- 3) Install outlet pipe in centre of precast outlet opening.
- 4) Standard steps conform to OPSD 405.010. Solid aluminum steps available upon request.
- 5) Please contact our sales department for pricing on precast drop structures.