



3000mm Reinforced Concrete Maintenance Holes

SIZE (mm)	DESCRIPTION	HEIGHT (m)	APPROX. MASS	PRICE \$
3000	flat cap	0.450	7847 kg/pc	5,389.00 ea.
3000 to 1200	transition slab c/w steps	0.450	7258 kg/pc	5,389.00 ea.
3000	riser c/w steps	0.610 to 2.438	7043 kg/m	4,620.30 /m
3000	base slab	0.305	8225 kg/pc	5,389.00 ea.
3000	safety grate supplied & installed			on request

3600mm Reinforced Concrete Maintenance Holes

SIZE (mm)	DESCRIPTION	HEIGHT (m)	APPROX. MASS	PRICE \$
3600	flat cap	0.450	10500 kg/pc	9,516.10 ea.
3600 to 1200	transition slab c/w steps	0.450	10500 kg/pc	9,516.10 ea.
3600	riser c/w steps	0.610 to 1.829	11042 kg/m	10,069.20 /m
3600	base slab	0.305	10500 kg/pc	9,516.10 ea.
3600	safety grate supplied & installed			on request

IMPORTANT: 2400mm, 3000mm, and 3600mm MAINTENANCE HOLES TO BE OFF-LOADED BY CONTRACTOR.

NOTES:

- 1) Gaskets included in price.
- 2) Prices on product manufactured to OPSD 700 series and OPSD 1000 series.
- 3) Install outlet pipe in centre of precast outlet opening.
- 4) Standard steps conform to OPSD 405.010. Solid aluminum steps available upon request.
- 5) Please contact our sales department for pricing on precast drop structures.

Maintenance Hole Appurtenances

DESCRIPTION	PRICE \$
maintenance hole safety steps OPSD 405.010	27.20 ea
solid aluminum steps OPSD 405.020	39.30 ea
outside rebar steps - supplied & installed fo C.I.P. drop structures	36.30 ea
maintenance hole clean out steps - supplied & installed	40.20 ea
maintenance hole frames & covers OPSD 401.010	671.60 ea
hatches cast into flat caps (hatch by others)	617.40 ea
swift lift lifting eyes (4 tonne capacity)	416.10 ea
swift lift lifting eyes (8 tonne capacity)	783.10 ea
engineering surcharge (non-standard engineering requirements)	983.90 ea

Maintenance Grade Rings

50mm maintenance hole grade ring - 12 per bundle - 52 kg ea.	46.50 ea
75mm maintenance hole grade ring - 8 per bundle - 75 kgs ea.	49.40 ea
75mm maintenance hole grade ring c/w step - 8 per bundle - 75 kgs ea.	72.60 ea
150mm maintenance hole grade ring - 150 kgs ea.	171.20 ea
300mm maintenance hole grade ring c/w step - 430 kgs ea.	219.20 ea
modutape (6.1 metres per roll)	16.50 /roll



CON CAST PIPE

Maintenance Hole Estimate Sheet

1200 mm DIAMETER

MONOBASE MH

DEPTH (m)		PRICE \$ /ea
FROM	TO	
1.37	1.52	2,108.00
1.53	1.68	2,225.00
1.69	1.85	2,344.00
1.86	2.01	2,460.00
2.02	2.17	2,577.00
2.18	2.33	2,444.00
2.34	2.50	2,563.00
2.51	2.66	2,680.00
2.67	2.82	2,796.00
2.83	2.98	2,914.00
2.99	3.15	3,031.00
3.16	3.31	3,148.00
3.32	3.47	3,267.00
3.48	3.63	3,383.00
3.64	3.80	3,500.00
3.81	3.96	3,616.00
3.97	4.12	3,734.00
4.13	4.28	3,968.00
4.29	4.45	4,086.00
4.46	4.61	4,203.00
4.62	4.77	4,320.00
4.78	4.99	4,437.00
5.00	5.15	6,074.00
5.16	5.31	6,309.00
5.32	5.48	6,427.00
5.49	5.64	6,545.00
5.65	5.80	6,661.00
5.81	5.96	6,778.00
5.97	6.13	6,896.00
6.14	6.29	7,012.00
6.30	6.45	7,128.00
6.46	6.61	7,129.00
6.62	6.78	7,246.00
6.79	6.94	7,365.00
6.95	7.10	7,481.00
7.11	7.26	7,716.00
7.27	7.43	7,833.00
7.44	7.59	7,948.00
7.60	7.75	8,066.00
7.76	7.91	8,184.00
7.92	8.08	8,301.00

1500 mm DIAMETER

MONOBASE MH

DEPTH (m)		PRICE \$ /ea
FROM	TO	
1.37	1.67	3,995.00
1.68	1.99	4,350.00
2.00	2.30	4,704.00
2.31	2.62	5,060.00
2.63	2.93	5,415.00
2.94	3.25	5,770.00
3.26	3.56	6,251.00
3.57	3.88	6,485.00
3.89	4.19	6,719.00
4.20	4.51	6,822.00
4.52	4.82	6,939.00
4.83	4.99	7,055.00
5.00	5.30	8,694.00
5.31	5.62	8,929.00
5.63	5.93	9,163.00
5.94	6.25	9,397.00
6.26	6.56	9,632.00
6.57	6.88	9,866.00
6.89	7.19	10,101.00
7.20	7.51	10,334.00
7.52	7.82	10,568.00
7.83	8.14	10,803.00